


运动员驻地酒店（三亚湾红树林度假酒店）配套服务功能设施临时改造费用预算												
序号	空间名称	改造项目	材质工艺	单价（元）	单位	数量	小计金额（元）	备注	图例			
1	代表团办理中心 面积：1746m²	墙面改造	墙面拆除 尺寸：250m²	¥85.00	m²	250	¥ 21,250.00		   			
			涂料环保乳胶漆：刷白 尺寸：1746m²	¥20.00	m²	1746	¥ 34,920.00					
		地面改造	地面凹凸清除	¥1,500.00	项	1	¥ 1,500.00					
			地面找平 水泥砂浆8cm 尺寸：1746m²	¥100.00	m²	1746	¥ 174,600.00					
			水泥基自流平面层 尺寸：1746m²	¥35.00	m²	1746	¥ 61,110.00					
		顶部改造	天花格栅吊顶 尺寸：1746m²	¥85.00	m²	1746	¥ 148,410.00					
		电路	线管材料 尺寸：1746m²	¥70.00	m²	1746	¥ 122,220.00					
			人工 尺寸：1746m²	¥85.00	m²	1746	¥ 148,410.00					
			灯具+开关+插座	¥35,000.00	项	1	¥ 35,000.00					
		房间隔断（16间房）	轻钢龙骨石膏板 尺寸：900m²	¥165.00	m²	900	¥ 148,500.00					
		局部修复	补洞拆除	¥20,000.00	项	1	¥ 20,000.00					
		垃圾清运保洁	现场卫生清理、清运	¥9,000.00	项	1	¥ 9,000.00					
		小计								¥ 924,920.00		
2	OCA办公室 面积：56m²	地面改造	地面凹凸清除	¥300.00	项	1	¥ 300.00		   			
			地面找平 水泥砂浆8cm 尺寸：56m²	¥100.00	m²	56	¥ 5,600.00					
			PVC仿木纹地板 尺寸：56m²	¥60.00	m²	56	¥ 3,360.00					
		墙面改造	涂料环保乳胶漆：刷白 尺寸：56m²	¥20.00	m²	56	¥ 1,120.00					
		顶部改造	轻钢龙骨石膏板 尺寸：56m²	¥165.00	m²	56	¥ 9,240.00					
		电路	线管材料 尺寸：56m²	¥70.00	m²	56	¥ 3,920.00					
			人工 尺寸：56m²	¥85.00	m²	56	¥ 4,760.00					
			灯具+开关+插座	¥2,000.00	项	1	¥ 2,000.00					
		窗户	玻璃贴 尺寸：13.4m²	¥90.00	m²	13.4	¥ 1,206.00					
		垃圾清运保洁	现场卫生清理、清运	¥500.00	项	1	¥ 500.00					
		小计								¥ 32,006.00		
		3	竞赛信息中心 面积：185.12m²	地面改造	地面凹凸清除	¥1,000.00	项	1		¥ 1,000.00		  
					地面找平 水泥砂浆8cm 尺寸：185.12m²	¥100.00	m²	185.12		¥ 18,512.00		
水泥基自流平面层 尺寸：185.12m²	¥35.00				m²	185.12	¥ 6,479.20					
墙面改造	涂料环保乳胶漆：刷白 尺寸：185.12m²			¥20.00	m²	185.12	¥ 3,702.40					
顶部改造	天花格栅吊顶 尺寸：185.12m²			¥85.00	m²	185.12	¥ 15,735.20					
电路	线管材料 尺寸：185.12m²			¥70.00	m²	185.12	¥ 12,958.40					
	人工 尺寸：185.12m²			¥85.00	m²	185.12	¥ 15,735.20					
	灯具+开关+插座			¥5,000.00	项	1	¥ 5,000.00					
垃圾清运保洁	现场卫生清理、清运			¥500.00	项	1	¥ 500.00					
小计							¥ 79,622.40					
					地面凹凸清除	¥1,000.00	项	1	¥ 1,000.00			

4	NOC服务中心 面积：551.29m²	地面改造	地面找平 水泥砂浆8cm 尺寸：551.29m²	¥100.00	m²	551.29	¥ 55,129.00		   
			水泥基自流平面层 尺寸：551.29m²	¥35.00	m²	551.29	¥ 19,295.15		
		墙面改造	涂料环保乳胶漆：刷白 尺寸：551.29m²	¥20.00	m²	551.29	¥ 11,025.80		
		顶部改造	天花格栅吊顶 尺寸：551.29m²	¥85.00	m²	551.29	¥ 46,859.65		
		电路	线管材料 尺寸：551.29m²	¥70.00	m²	551.29	¥ 38,590.30		
			人工 尺寸：551.29m²	¥85.00	m²	551.29	¥ 46,859.65		
			灯具+开关+插座	¥12,000.00	项	1	¥ 12,000.00		
		楼梯改造	楼梯扶手	¥385.00	m	16	¥ 6,160.00		
		垃圾清运保洁	现场卫生清理、清运	¥500.00	项	1	¥ 500.00		
		小计					¥ 237,419.55		
5	综合门诊中心 面积：604m²	地面改造	地面凹凸清除	¥1,000.00	项	1	¥ 1,000.00		  
			地面找平 水泥砂浆8cm 尺寸：604m²	¥100.00	m²	604	¥ 60,400.00		
			水泥基自流平面层 尺寸：604m²	¥35.00	m²	604	¥ 21,140.00		
			露台修复 尺寸：180m²	¥450.00	m²	180	¥ 81,000.00		
		墙面改造	外墙隔断：夹芯彩钢板 尺寸：320m²	¥160.00	m²	320	¥ 51,200.00		
			隔断-轻钢龙骨石膏板 尺寸：600m²	¥165.00	m²	600	¥ 99,000.00		
			涂料环保乳胶漆：刷白 尺寸：302m²	¥20.00	m²	302	¥ 6,040.00		
			涂料环保乳胶漆：刷白 尺寸：302m²	¥40.00	m²	302	¥ 12,080.00	对二楼原有红色乳胶漆处理覆盖	
		顶部改造	天花格栅吊顶 尺寸：604m²	¥85.00	m²	604	¥ 51,340.00		
		电路	线管材料 尺寸：604m²	¥70.00	m²	604	¥ 42,280.00		
			人工 尺寸：604m²	¥85.00	m²	604	¥ 51,340.00		
			灯具+开关+插座	¥10,000.00	项	1	¥ 10,000.00		
		上下水改造	上下水管材+人工	¥15,000.00	项	1	¥ 15,000.00		
		楼梯改造	楼梯扶手	¥385.00	m	45	¥ 17,325.00		
			楼梯翻新油漆	¥10,000.00	项	1	¥ 10,000.00		
		门洞处理（5个）	轻钢龙骨石膏板	¥165.00	m²	130	¥ 21,450.00		
		垃圾清运保洁	现场卫生清理、清运	¥500.00	项	1	¥ 500.00		
		小计					¥ 551,095.00		
6	隔离楼 面积：85.56m²	地面改造	地面凹凸清除	¥1,000.00	项	1	¥ 1,000.00		  
			地面找平 水泥砂浆8cm 尺寸：85.56m²	¥100.00	m²	85.56	¥ 8,556.00		
			水泥基自流平面层 尺寸：85.56m²	¥35.00	m²	85.56	¥ 2,994.60		
		墙面改造	隔断-轻钢龙骨石膏板 尺寸：50m²	¥165.00	m²	50	¥ 8,250.00		
			涂料环保乳胶漆：刷白 尺寸：85.56m²	¥20.00	m²	85.56	¥ 1,711.20		
		顶部改造	天花格栅吊顶 尺寸：85.56m²	¥85.00	m²	85.56	¥ 7,272.60		
		电路	线管材料 尺寸：85.56m²	¥70.00	m²	85.56	¥ 5,989.20		
			人工 尺寸：85.56m²	¥85.00	m²	85.56	¥ 7,272.60		
			灯具+开关+插座	¥3,000.00	项	1	¥ 3,000.00		
		上下水改造	上下水管材+人工	¥8,000.00	项	1	¥ 8,000.00		
		垃圾清运保洁	现场卫生清理、清运	¥500.00	项	1	¥ 500.00		
		小计					¥ 54,546.20		
		地面改造	地面凹凸清除	¥1,000.00	项	1	¥ 1,000.00		
			地面找平 水泥砂浆8cm 尺寸：88.2m²	¥100.00	m²	88.2	¥ 8,820.00		
			水泥基自流平面层 尺寸：88.2m²	¥35.00	m²	88.2	¥ 3,087.00		

7	中医馆 面积：88.2m²	墙面改造	隔断-轻钢龙骨石膏板 尺寸：50m²	¥165.00	m²	50	¥ 8,250.00		
			涂料环保乳胶漆：刷白 尺寸：88.2m²	¥20.00	m²	88.2	¥ 1,764.00		
		顶部改造	天花格栅吊顶 尺寸：88.2m²	¥85.00	m²	88.2	¥ 7,497.00		
		电路	人工 尺寸：88.2m²	¥85.00	m²	88.2	¥ 7,497.00		
			线管材料 尺寸：88.2m²	¥70.00	m²	88.2	¥ 6,174.00		
			灯具+开关+插座	¥3,000.00	项	1	¥ 3,000.00		
		上下水改造	上下水管材+人工	¥8,000.00	项	1	¥ 8,000.00		
		垃圾清运保洁	现场卫生清理、清运	¥500.00	项	1	¥ 500.00		
小计							¥ 55,589.00		
8	媒体分中心和访客中心 (椰林酒店1层)	入住服务台—通道隔断	行架隔墙+喷绘布 尺寸：117.6m²	¥110.00	m²	117.6	¥ 12,936.00		
		访客中心—休息室隔断 (两间房)	万向轮可移动屏风 尺寸：96m²	¥350.00	m²	96	¥ 33,600.00		
		媒体分中心—功能区隔断	万向轮可移动屏风 尺寸：81.7m²	¥350.00	m²	81.7	¥ 28,595.00		
			行架隔墙+喷绘布 尺寸：169.8m²	¥110.00	m²	169.8	¥ 18,678.00		
		工作人员餐厅—通道隔断	行架隔墙+喷绘布 尺寸：121.5m²	¥110.00	m²	121.5	¥ 13,365.00		
		小计					¥ 107,174.00		
9	交通调度室及驾驶室休息室 面积：346m²	电路	人工 尺寸：346m²	¥85.00	m²	346	¥ 29,410.00		
			线管材料 尺寸：346m²	¥70.00	m²	346	¥ 24,220.00		
			灯具+开关+插座	¥8,000.00	项	1	¥ 8,000.00		
		墙面改造	隔断-轻钢龙骨石膏板 尺寸：170m²	¥165.00	m²	130	¥ 21,450.00		
		小计					¥ 61,630.00		
10	咖啡店 面积：96m²	地面改造	地面凹凸清除	¥1,000.00	项	1	¥ 1,000.00	 	
			地面找平 水泥砂浆8cm 尺寸：96m²	¥100.00	m²	96	¥ 9,600.00		
			水泥基自流平面层 尺寸：96m²	¥35.00	m²	96	¥ 3,360.00		
		墙面改造	涂料环保乳胶漆：刷白 尺寸：96m²	¥20.00	m²	96	¥ 1,920.00		
		顶部改造	天花格栅吊顶 尺寸：96m²	¥85.00	m²	96	¥ 8,160.00		
		电路	人工 尺寸：96m²	¥85.00	m²	96	¥ 8,160.00		
			线管材料 尺寸：96m²	¥70.00	m²	96	¥ 6,720.00		
			灯具+开关+插座	¥5,000.00	项	1	¥ 5,000.00		
		上下水改造	上下水管材+人工	¥8,000.00	项	1	¥ 8,000.00		
		垃圾清运保洁	现场卫生清理、清运	¥500.00	项	1	¥ 500.00		
		小计					¥ 52,420.00		
总计							¥ 2,156,422.15		
税费(9%)							¥ 194,077.99		
(此总金额包含人工、材料)合计							¥ 2,350,500.14		